BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/06/2013-14, Date:05.11.2013 **ITEM NO: 55**

SCHEDULE-B

NAME OF WORK: Improvements to Road, Drain, Foot path BTS Layout & Sheshadri Layout in Bagalagunte ward No 14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **RAVIKUMAR B T .**		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	9
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	709.31	86.03	Rupees Eighty Six and Three Paise Only	61021.94
2	Removing B.S.Slab of drain and stacking etc., complete as per specifications.	Sqm	83.97	47.52	Rupees Forty Seven and Fifty Two Paise Only	3990.25
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	24.49	3993.65	Rupees Three Thousand Nine Hundred Ninety Three and Sixty Five Paise Only	97804.49
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	11.47	4448.0	Rupees Four Thousand Four Hundred Forty Eight Only	51018.56
5	Refixing stone slabs of drains and pointing in CM 1:3 etc., complete as per specifications.	Sqm	83.97	66.42	Rupees Sixty Six and Forty Two Paise Only	5577.29
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete as per specifications.	Sqm	55.98	325.68	Rupees Three Hundred Twenty Five and Sixty Eight Paise Only	18231.57

B T Ravikumar

Signature of the Contractor

Executive Engine